KARTAVYA ENTERPRISE

Shed No.1, Near Vinayak Engineering, Veraval Rajkot, Gujrat- 360001. Phone: +91 9714516593

Email: kartavyaenterprise87@gmail.com



QUOTATION

DATE : QUOTATION # CUSTOMER ID VALID UNTILL 6/22/2023 1664 1664 7/7/2023

CUSTOMER NAME

TO, BHARATBHAI TURBO TECH.

Subject: Quotation for Application of 3MM EPOOXY flooring

DESCRIPTION	Sq. ft	Rate/Sq.ft/Ru.Feet	Amount
Step 1: Surface Preparation: Manual for mechanical surface preparation by grinding the surface and then removing loose particles	Sgft.	75	75.00
Step 2: Hair Line Cracks: Hair Line cracks will be opened and will be filled by puttuy.	34.11		,0100
Step 3: Application Of Primar: An primar will be applied on the dust free surface, it will be act as base for the On coming treatment, primar will be cured within 6 to 8 hrs.it will be allowed tocured completely.			
Step 4: Application Of 2 mm Screed Coat: Application of Screed will be cured within 8 to 10 hrs. will be allowed to cured completely.			
Step 5:Application Of 1 mm Epoxy Toap Coat: Application of Epoxytop coat will be cured within 8 to 10 hrs. will be allowed to cured completely.			
Step 6: yellow marking	ruft.	15.00	15.00
Note: 3years warranty of floor debonding			

Subtotal

ADD GST TAX 18%

TERMS & CONDITIONS:

- 1. The above work should be carried under the supervision of applicator.
- 2. The above rates are valid for 15 days only.
- 3. Area Calculation Should be based on the quality of Floor ie; Floor Level, Undulations and Other Debries on floor seen visually. Exception of area under machine perifery will be calculated extra in case of area of that particular perifery is more than 40Sq.feet.
- 4. Food & Accomodation will in Scope of mother dairy.
- 5. 70% in advance and balance 30% After work completion.
- 6. Work schedule will be given after deposition of advance amount.

14 / 12'	<i>''</i>	7777777	40268

TOTAL	